


BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division, SCHDULE-B

Name of Work: Construction of culverts at Kammagondanahalli area in Shettyhalli Sub-Division, Ward No-12,
Under 22.75% grant

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	260.16	109.18	Rupees One Hundred Nine and Eighteen Paise Only
2	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	29.27	3153.5	Rupees Three Thousand One Hundred Fifty Three and Fifty Paise Only
3	Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	117.07	2776.14	Rupees Two Thousand Seven Hundred Seventy Six and Fourteen Paise Only
4	Providing and laying in position plain cement concrete of mix 1:2:4 using 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	13.01	3845.68	Rupees Three Thousand Eight Hundred Forty Five and Sixty Eight Paise Only
5	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Cum	195.12	57.13	Rupees Fifty Seven and Thirteen Paise Only
6	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-15 (1:2:4) for raft foundation, column footing, main and secondary beams. complete as per specifications.	Cum	44.88	4386.28	Rupees Four Thousand Three Hundred Eighty Six and Twenty Eight Paise Only


Technical Manager-2
Signature of the Contractor
KRIDL, BBMP, Bangalore


Executive Engineer

7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Q	53.85	5031.14	Rupees Five Thousand Thirty One and Fourteen Paise Only
8	Conveying the excavated earth to a distance of 2kms with all lead & lifts including loading & unloading charges etc., complete as per specifications.	Cum	214.00	71.338	Rupees Seventy One and Thirty Three Paise Only


Technical Manager-2
Signature of the Contractor
KRIDL, BBMP, Bangalore


Executive Engineer,
Dasarahalli Division,